

INDIAN INSTITUTE OF MANAGEMENT NAGPUR

Tender No : IIMN/CAO/ 05 /2018-19 dated 23/05/2018

Name of work :Electrification work at EBC hostel for temporary hostel accommodation of IIMN

**Price bid part-II**

Sr.no	Description	Qty	Unit	Rate	Amount
1	Point wiring in PVC trunking (Casing-capping with 1.0 sq.mm FR grade copper wire with modular type switch and required accessories	200	Point		
2	Wiring for plug on board with modular switch socket with copper wiring and earthing	60	Point		
3	Supplying and erecting PVC trunking (casing-n-capping) of size 32 mm with accessories on wall / ceiling	1100	Mtr		
4	Supply and erecting mains with 2 x 2.5 Sq.mm F.R. copper PVC insulated wire laid in provided conduit/trunking/inside pole /bus bars or any other places	1500	Mtr		
5	Supplying and fixing modular type electronic fan regulator on the existing plate switch box including connections.	60	Each		
6	Supplying and erecting LED lamp 5 watt	120	Each		

Sr.no	Description	Qty	Unit	Rate	Amount
7	Supply and erecting static energy meter 230V, 50 cycle AC supply 5/10/20/40 A class/accuracy I.S.I. marked with metal/polycarbonate enclosure meter with :CD/LED display complete erected on polished TW board duly wired with required size of weather proof PVC wires duly tested for class-II accuracy by electric supply company	1	Each		
8	Supplying and erecting Flexible conduit of Size 32 mm	10	Mtr		
9	Supplying and erecting PVC gland of size 32 mm	6	Each		
10	Supplying and erecting mains with 4 x 16 sq mm F.R. Standard/solid copper PVC insulated wire laid in provided conduit/trunking/inside pole/bus bar or any other places	15	Mtr		
11	Supplying and erecting A.C box with single pole MCB of 25 Amp	5	Each		
12	Supplying and erecting mains with 2 x 4 sq mm F.R. Standard/solid copper PVC insulated wire laid in provided conduit/trunking/inside pole/bus bar or any other places	100	Mtr		
13	Supplying, erecting single pole MCB of 6A to 32A, B-series (for motor/power) in provided distribution board	5	Each		

Sr.no	Description	Qty	Unit	Rate	Amount
14	Supplying and erecting copper lugs upto 16 sq.mm	20	Each		
15	Supplying and erecting modular 16/20 Amp switch	10	Each		
16	Supplying and erecting modular 16/20 Amp socket	10	Each		
17	Supplying and erecting modular Dummy plate	13	Each		
18	Supplying and erecting modular 6 M Box	11	Each		
19	Supplying & erecting PVC gland 25 mm	9			
20	Supplying & erecting 4 way TPND B	1	Each		
21	Supplying & erecting 63 A 4 pole MCB	1	Each		
22	Supplying and erecting modular 16/10 Amp switch	30	Each		
23	Supplying and erecting modular 16/10 Amp socket	30	Each		

Sr.no	Description	Qty	Unit	Rate	Amount
24	Supplying and erecting 4 pole MCCB 100 Amp	2	Each		
25	Supplying and erecting encloser box for 4 pole MCCB 100 Amp	2	Each		
26	Supplying and erecting spreader link for 4 pole MCCB	16	Each		
27	Supplying and erecting 2 pole MCB 6 to 32 AMP	2	Each		
28	Supplying and erecting 2 pole MCB 40 to 63 AMP	2	Each		
29	Supplying and erecting mains with 4 X10 sq.mm	5	Mtr		
				Total Amount	
				Add % GST	
				Grand Total	

Note:

- 1 All rates are to be quoted excluding the GST applicable. The GST will be paid in addition to the total amount payable.
- 2 The above quantity may vary as per actual requirement of Site.