

INDIAN INSTITUTE OF MANAGEMENT NAGPUR

Tender No : IIMN/CAO/ 01 /2018-19 dated 14/05/2018

Name of work :Dismantling & Painting at EBC Hostel for temporary hostel accommodation of IIMN

**Price bid part-II**

Sr.no	Description	Qty	Unit	Rate	Amount
1	Dismantling stone/Kaddapp slab flooring laid in cement mortar including stacking of serviceable material and disposal of unserviceable material within 50 metres lead	300	Sq.m		
2	Demolishing brick work manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-charge. In cement mortar	40	Cu.m		
3	15 mm cement plaster on rough side of single or half brick wall of mix:(1 cement: 4 coarse sand)	270	Sq.m		
4	Distempering with oil bound washable distemper of approved brand and manufacture to give an even shade New work (two or more coats) over and including water thinnable priming coat with cement primer	300	Sq.m		
5	Transportation of material obtained from debris of various sorts including necessary excavation/ loosing including loading,unloading and conveying and disposing as directed.	40	Cu.m		
				Total Amount	
				Add % GST	
				Grand Total	

Note:

- 1 All rates are to be quoted excluding the GST applicable. The GST will be paid in addition to the total amount payable.
- 2 The above quantity may vary as per actual requirement of Site.