

INDIAN INSTITUTE OF MANAGEMENT NAGPUR

Tender No : IIMN/CAO/03/2018-19 dated 17-05-2018

Name of work :Conversion of existing classroom to tiered classroom at IIM Nagpur

**Price bid part-II**

Sr.no	Description	Qty	Unit	Rate	Amount
1	Providing, and fixing at site 25mm thick Plywood as per the drawing or as directed, including all necessary fixtures, hardware, and accessories, etc. complete.	25.00	Sq.m		
2	Providing, and fixing at site 1 mm thick laminate of approved colour as directed, including all necessary fixtures, hardware, and accessories, etc. complete.	7.00	Sq.m		
3	Brick work with non modular fly ash bricks conforming to IS:12894, class designation 10 average compressive strength in super structure above plinth level up to floor V level in 6.34.2 Cement mortar 1:6 (1 cement : 6 Coarse sand)	20.00	Cu.m		
4	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level 1:3:6 (1 Cement : 3 coarse sand (zone-III) : 6 graded stone aggregate 20 mm nominal size).	8.00	Cu.m		

Sr.no	Description	Qty	Unit	Rate	Amount
5	Providing and laying vitrified floor tiles in different sizes (thickness to be specified by the manufacturer) with water absorption less than 0.08% and conforming to IS: 15622, of approved make, in all colours and shades, laid on 20mm thick cement mortar 1:4 (1 cement : 4 coarse sand), jointing with grey cement slurry @ 3.3kg/sqm including grouting the joints with white cement and matching pigments etc., complete. joints with white cement and matching pigments etc., complete.11.41.2 Size of Tile 600x600 mm	105.00	Sq.m		
6	Providing and laying Vitrified tiles in different sizes (thickness to be specified by manufacturer), with water absorption less than 0.08 % and conforming to I.S. 15622, of approved make, in all colours & shade, in skirting, riser of steps, over 12 mm thick bed of cement mortar 1:3 (1 cement: 3 coarse sand), jointing with grey cement slurry @ 3.3kg/sqm including grouting the joint with white cement & matching pigments etc. complete. 11.46.2 Size of Tile 600x600 mm	10.00	Sq.m		
7	Dismantling stone slab flooring laid in cement mortar including stacking of serviceable material and disposal of unserviceable material within 50 metres lead	105.00	Sq.m		
8	Dismantling doors, windows and clerestory windows (steel or wood) shutter including chowkhats, architrave, holdfasts etc. complete and stacking within 50 metres lead : 15.12.1 Of area 3 sq. metres and below	1.00	Sq.m		

Sr.no	Description	Qty	Unit	Rate	Amount
9	Taking out doors, windows and clerestory window shutters (steel or wood) including stacking within 50 metres lead :	1.00	Each		
10	Wall painting with premium acrylic emulsion paint of interior grade, having VOC (Volatile Organic Compound) content less than 50 grams/ litre of approved brand and manufacture, including applying additional coats wherever required to achieve even shade and colour 13.83.2 Two coats	65.00	Sq.m		
				Total	
				Add % GST	
				Grand Total	

Note:

- 1 All rates are to be quoted excluding the GST applicable. The GST will be paid in addition to the total amount payable.
- 2 The above quantity may vary as per actual requirement of Site.