

Name of work:Supply, Installation Testing and Commissioning of Split Air conditioners for hostel block E and classroom block at IIMN Nagpur

Price bid part-II

Sr.no	Description	Qty	Unit	Rate	Amount
1	Supplying, installation, testing and commissioning of following capacity Hyper Tropical wall mounted Split Type Air Conditioner with remote having rotary compressor, machine designed upto 52 deg .C.with advance filters, operating on refrigerent-410 A, for 230 V 50 Hz single phase A/C supply,capable of performing the function as cooling, dehumidifying, air circulation i/c all standard accessories and MS stand for outdoor unit with following capacity cooling etc complete as required.				
	a)2.0 TR (3 star) Toshiba-RAS-24S3KS-IN +RAS-24S3AS-IN(OR Similar Make in O general model OR Mitsubishi OR DAIKIN	6	No		
	b)1.1 TR (5 Star)(Make:Toshiba Inverter Split AC Model:RAS-13N3KCV-IN or similar in Diakin/Mitsubishi/O General)	4	No		
2	Supplying and fixing of Extra copper piping of size 5/8" and 1/4" with nitrile rubber insulation from indoor unit to outdoor unit of 2 TR with all accessories etc. complete as required.	30	MTR		

Sr.no	Description	Qty	Unit	Rate	Amount
3	Supplying and fixing of Extra copper piping of size 3/8" and 1/4" with nitrile rubber insulation from indoor unit to outdoor unit of 1.0 TR with all accessories etc. complete as required.	30	MTR		
4	Supplying and fixing of 3 core 4 sq.mm. PVC insulated PVC sheathed copper conductor cable on surface of wall/ceiling for connection between indoor & Outdoor unit beyond standered length of 6.0 m etc as required.	20	MTR		
5	Supplying, Installation, Testing and commissioning of UPVC drain Piping of following sizes with adequate supports as per specifications and instructions of Engineer-in charge.(a) 25 mm dia (Plasto, Finolex,Supreme)	30	MTR		
6	Supplying and fixing of 3 core 4 sq.mm. PVC insulated unarmoured copper conductor cable for indoor to outdoor PCB supply confirming to confirming to IS:1554(Part-1) on surface etc. complete as required. (Finolex/Rcable/Havells)	15	MTR		
				Total Amount	
				Add % GST	
				Grand Total	

Note:

- 1 All rates are to be quoted excluding the GST applicable. The GST will be paid in addition to the total amount payable.
- 2 The above quantity may vary as per actual requirement of Site.